



NO.	REVISIONS	APPROVED	DATE



NOTES:

1. THIS DRIVEWAY DESIGN SHALL BE USED FOR PARKING LOTS WITH 100 VEHICULAR SPACES OR GREATER.
2. ALL DRIVEWAYS SHALL BE CONSTRUCTED WITH 6" THICK CLASS 560-C-3250 PORTLAND CEMENT CONCRETE
3. WEAKENED-PLANE JOINTS SHALL BE INSTALLED AT BOTH SIDES OF ALL DRIVEWAYS AND AT APPROXIMATELY 10' (MAX.) INTERVALS.
4. W = 32' MINIMUM.
5. RADIUS SHALL BE A MINIMUM OF 12'.

<p align="center">CITY OF PALM SPRINGS PUBLIC WORKS & ENGINEERING DEPARTMENT</p>	<p>APPROVED: <i>DBch</i> DATE: <u>5/8/12</u></p>	<p align="center">28931</p>
	<p>CITY ENGINEER</p>	<p align="center">R.C.E.</p>
<p align="center">PARKING LOT ENTRANCE</p>	<p>DRAWN BY: G.F.F.</p>	<p>FILE NO. STANDARDS</p>
	<p>CHECKED BY: M.L.F.</p>	<p>DWG. NO. 205</p>